



KENYA ELECTRICITY GENERATING COMPANY PLC.

KGN-TURK-02-2019.

TENDER FOR CONSTRUCTION OF NEW MESS AT TURKWEL POWER STATION.

23<sup>rd</sup> January, 2019.

ADDENDUM NO 1.

In Accordance with the Tender for “Construction of New Mess at Turkwel Power Station.” KenGen hereby Wishes to make the following changes for the above tender through Addendum No.1

Omit *Item G and Item H under Bill No. 8* in the original BOQ and replace it with *Item P and Item Q under Bill No. 8* elucidated hereunder. *Add Item P and Item Q under Bill No. 8 (new Bill Item)* below as part of the BOQ items.

BILL 8					
	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<b>CEILING</b>				
	<i>Supply all materials and lay to approval</i>				
P	Provide & fix at site plain Gypsum Board false ceiling made out of 12.5 mm thick reinforced gypsum board sheets to be fixed with main frame channels of size(80 mm x 26 mm x 0.5 mm) at every 450 mm c/c, intermediate channels of size(15 mm x 45 mm x 0.9 mm) at every 1220 mm c/c with perimeter channel 20 mm x 26 mm x 0.5 mm all along the wall shall be provided . The frame work to be suspended with strap bolts as recommended using rail plugs 12.5mm dia x 35 mm long with 6 mm dia bolt and soffit cleat. Paint Cieling surface with two coats of paint to get a smooth & even look including the cost of hard ware fittings,all labour & materials.	SM	1500		
Q	25 x 75mm wrot cypress covetto moulded cornice plugged	LM	342		

ACKNOWLEDGEMENT OF ADDENDUM NO 1.

We, the undersigned hereby certify that the Addendum is an integral part of the document and has been incorporated in the tender proposal.

Signed.....

Tenderer.....

Date.....