



KenGen

KENYA ELECTRICITY GENERATING COMPANY LIMITED

KGN-SONDU -012- 2017

TENDER FOR REPLACEMENT OF POLES FOR 11kV INTAKE OVERHEAD LINE (PHASE III) AT SONDU MIRIU POWER STATION

15TH November 2017

ADDENDUM NO. 1:

In accordance with the tender mentioned above, KenGen hereby issue addendum No. 1:

I. ADDENDUM

A. CHANGES TO BILL OF QUANTITIES

- **Include additional bill items** as follows:

ELEMENT 10: EXTERNAL WORKS

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
				Kshs.	Kshs.
1	Removal of wooden pole and replacement with concrete pole complete with galvanized steel cross arms, insulators and all other fittings and accessories. (transport, labour, tests inclusive)	PC	83		
2	Tap link isolator and accessories	PC	2		

II. CLARIFICATION

BILL REF NO.	QUERY	PROCURING ENTITY'S RESPONSE	REQUIREMENT FOR ADDENDUM
1	You have indicated that the number of poles	The additional two (2) poles are for mounting the tap link isolator for the Base Camp 11kV line	This clarification requires an addendum on

	will have to be increased. Please clarify		the quantity of poles from 81 to 83 as captured above
2	You have indicated that the tap link Isolators	Replace one Isolation Point with Tap Link Isolator at Power House for Base Camp 1 1kV Line. The specifications for this remains as initially captured in the tender document	This clarification requires an addendum on the quantity of Tap Link Isolators and Accessories from 1 to 2 as captured above

ACKNOWLEDGEMENT OF ADDENDUM NO.1

We, the undersigned hereby certify that the addendum is an integral part of the document and the alterations set out in addendum have been incorporated in the tender proposal.

Signed

Tenderer